

**QUOTE #QWBXR8****Place of Supply:**Brindavan Nagar, Tavarekere 5th Cross Road BTM Layout
Stage 1 Bangalore Karnataka 560029**INT360 DESIGN****Quotation Date**

12/05/2026

Expiration

Until 11/06/2026

Sales Person

Nandini

EXECUTION PARTNER:**Kalyan****Email:** kalyan.suram@int360.in**Phone:** 9243555345**Address:** Brindavan Nagar, Tavarekere 5th Cross Road
BTM Layout Stage 1 Bangalore Karnataka
560029**CLIENT:****Manoj Kumar****Bill To:**B-13112, Sobha Pavalion, 3, Sarjapur Main Road,
Sarjapur Marathahalli Road , Bengaluru Urban,
Karnataka, 560035**Ship To:**B-13112, Sobha Pavalion, 3, Sarjapur Main Road,
Sarjapur Marathahalli Road , Bengaluru Urban,
Karnataka, 560035**Account Name:** EROEI Tech Pvt Ltd
Account Number: 50200099247266
Branch: Malleshwaram, Bangalore**Bank Name:** HDFC (Current account)
IFSC Code: HDFC0000041
UPI ID: tatvaops@ibl**Registered Address** B302, Renaissance Park 1, Malleshwaram (W), Bangalore - 560055**GSTIN** 29AAICE3771F1ZG**Phone** 8056539544**Email** contact@tatvaops.com**Website** www.tatvaops.com**Interiors**

#	DESCRIPTION	QT	RATE (Rs.)	PRICING	AMOUNT (Rs.)
1	Base Unit Kitchen SAC: 9983 Lower unit +Island Century Sainik BWP 710 16mm	41.83	1,960.00	Area (in sqft)	96,744.42

2	Base Unit Kitchen SAC: 9983 Middle unit Century Sainik BWP 710 16mm	19.88	1,960.00	Area (in sqft)	45,978.46
3	Loft Kitchen SAC: 9983 Loft Century Sainik MR 303 16mm	41.8	1,160.00	Area (in sqft)	57,215.84
4	Crockery Units Kitchen SAC: 9983 PVC Tray and Thalli	1	2,500.00	Area (in sqft)	2,950.00
5	Tandem Pullouts Kitchen SAC: 9983 Bottle pullout tandem style	1	5,800.00	Area (in sqft)	6,844.00
6	Tandem Pullouts Kitchen SAC: 9983 Tandem channels	5	4,500.00	Area (in sqft)	26,550.00
7	Base Unit Utility SAC: 9983 Lower unit +Island Century Sainik BWP 710 16mm	15.4	1,960.00	Area (in sqft)	35,617.12
8	Base Unit Utility SAC: 9983 Middle unit Century Sainik BWP 710 16mm	11	1,960.00	Area (in sqft)	25,440.80
9	Accessories Kitchen / Granite SAC: 9983 Kitchen +utility	33	790.00	Area (in sqft)	30,762.60
10	Accessories Kitchen / Granite SAC: 9983 Kitchen sink 16"x18" SS Futura	1	5,400.00	Area (in sqft)	6,372.00
11	Shoe Rack Foyer SAC: 9983	12	1,750.00	Area (in sqft)	24,780.00

12	Wall Decor Foyer SAC: 9983 Wall decor lumpsum	1	20,000.00	Per Unit	23,600.00
13	Console unit Foyer SAC: 9983 Console table	6	1,750.00	Area (in sqft)	12,390.00
14	TV Units Living Room SAC: 9983 TV unit lower storage	14	1,750.00	Area (in sqft)	28,910.00
15	TV Units Living Room SAC: 9983 TV back wall decore lumpsum	1	22,000.00	Per Unit	25,960.00
16	Crockery Units Dining SAC: 9983 Crockery lower storage +wall storage	16.8	1,750.00	Area (in sqft)	34,692.00
17	Pooja Unit Dining SAC: 9983 Pooja unit	14	1,750.00	Area (in sqft)	28,910.00
18	Wardrobe Bedroom 1 SAC: 9983 Wardrobe Century Sainik MR303	42	1,750.00	Area (in sqft)	86,730.00
19	Loft Bedroom 1 SAC: 9983 Century Sainik MR303 16mm	13.2	1,160.00	Area (in sqft)	18,068.16
20	Vanity Units Bedroom 1 SAC: 9983 Vanity in bathroom With plain mirror	5	1,960.00	Area (in sqft)	11,564.00
21	Vanity Units Bedroom 1 SAC: 9983 Small Mirror storage both side	3	1,960.00	Area (in sqft)	6,938.40

22	Partitions Bathroom SAC: 9983 Glass partition fixed glass	1	12,000.00	Per Unit	14,160.00
23	Storage Solutions Bathroom SAC: 9983 Wall vanity box	9	1,960.00	Area (in sqft)	20,815.20
24	Wardrobe Bedroom 2 SAC: 9983 Wardrobe Century Sainik MR303 with mirror on door	45.5	1,750.00	Area (in sqft)	93,957.50
25	Loft Bedroom 2 SAC: 9983 Loft Century Sainik MR 303 16mm	15.4	1,160.00	Area (in sqft)	21,079.52
26	Dressing Unit Bedroom 2 SAC: 9983 Dressing storage for dressing	14	1,750.00	Area (in sqft)	28,910.00
27	TV Units Bedroom 2 SAC: 9983 TV unit with lower storage and tall storage	6	1,750.00	Area (in sqft)	12,390.00
28	Vanity Units Bathroom SAC: 9983 Loft Century Sainik MR 303 16mm	5	1,960.00	Area (in sqft)	11,564.00
29	Partition Walls Bathroom SAC: 9983 Glass partition lumpsum (fixed galss)	1	12,000.00	Per Unit	14,160.00
30	Vanity Units Bathroom SAC: 9983 Wall Vanity box	9	1,960.00	Area (in sqft)	20,815.20

31	Vanity Units Bathroom SAC: 9983 Small Mirror storage both side	3	1,960.00	Area (in sqft)	6,938.40
32	Wardrobe Bedroom 3 SAC: 9983 Wardrobe Century Sainik MR303 with dressing	63	1,750.00	Area (in sqft)	1,30,095.00
33	Loft Bedroom 3 SAC: 9983 Loft Century Sainik MR 303 16mm	26.4	1,160.00	Area (in sqft)	36,136.32
34	Study Table Bedroom 3 SAC: 9983 Study table with drawer	6	1,750.00	Area (in sqft)	12,390.00
35	Study Table Bedroom SAC: 9983 Side ledges	6.4	1,160.00	Area (in sqft)	8,760.32
36	Vanity Units Bathroom SAC: 9983 Vanity in bathroom With plain mirror	5	1,960.00	Area (in sqft)	11,564.00
37	Partition Walls Bathroom SAC: 9983 Glass partition lumpsum (fixed glass)	1	12,000.00	Per Unit	14,160.00
38	Partition Walls Bathroom SAC: 9983 Small Mirror storage both side	3	1,960.00	Area (in sqft)	6,938.40
39	Electrical Work Electrical SAC: 9983 Considering lumpsum, may vary on design and num of point shiftings	1	45,000.00	Per Unit	53,100.00

40	Accessories Hardware SAC: 9983 Hettich hinges soft close	65	280.00	Per Unit	21,476.00
41	Accessories Hardware SAC: 9983 Hettich Channels soft close	20	850.00	Per Unit	20,060.00
42	Accessories cleaning SAC: 9983 Deep cleaning	1	10,000.00	Per Unit	11,800.00
43	Painting Painting SAC: 9983 TBD	1	1.00	Area (in sqft)	0.00
44	Plumbing Plumbing SAC: 9983 Extra work in kitchen or other areas on actuals TBD	1	1.00	Area (in sqft)	0.00
45	Accessories Curtain Rods SAC: 9983 Rod length to be decided on window sizes	1	1.00	Area (in sqft)	0.00

Subtotal	10,23,972.60
Less: Discount	1,84,316.00
TatvaOps Service Charges	10,239.73
Taxable Amount	1,86,158.22
GRAND TOTAL	10,36,054.54

Tax & Charges Breakdown

GST %	GST TYPE	AMOUNT (Rs.)
18%	SGST	Rs.92,157.54
18%	CGST	Rs.92,157.53
18%	GST on TatvaOps Charges	Rs.1,843.15
Total Taxable Amount		Rs.1,86,158.22

Dependencies & Exclusions

Exclusions

Material specification:

- The ply used for the kitchen carcass is BWP 710 Grade Century Sainik.
- The ply used for other carcass is MR 303 Grade Century Sainik.
- All hinges and channels are from Hettich/EBCO, soft closing, unless specified. Additional charges: Hinges Ebco: ₹180; Hinges Hettich: ₹380; Channels Ebco: ₹690; Channels Hettich: ₹850 ; Loft hinges and Wardrobe internal drawers will be normal closing unless specified.
- Ply used for Side and Middle Panels will be 16mm Ply with 18mm output and Back Panel will be 6mm Ply.
- Ply used for Swing Doors will be 18mm Ply / 16mm Ply or HDHMR (based on customer discussion), and Ply used for Sliding Doors will be with Block boards or HDHMR (20mm/18mm).
- Door Stiffeners cost will be Added based on door size (additional charges apply).
- External finish for wardrobe: Laminates of Merino, Century, Welvin, or equivalent (High Glossy/Textured), up to ₹1500 included in the per sq. ft. cost. • Internal finish: 0.8mm standard laminate – off white, fabric laminate will be charged additional.
- All SS baskets are from 304-grade rust-proof material.
- Locks will be from Godrej, Europa, or Ebco (subject to availability).
- Hydraulic lift-ups will be from Ebco unless mentioned in the quotation.
- Push magnets: will be from Ebco unless mentioned in the quotation.
- False ceiling: POP-Gypsum board from Saint Gobain with ultra-channels, measured on an RFT (running square feet) basis. Asian Premium emulsion paint will be considered for gypsum areas. Electrical work is additional if not included in the quotation.
- Mirrors/Glass: From Saint Gobain.
- Handles: Cost range included for Loft areas: ₹100-130; Wardrobes: ₹180-200; Any Customized handles or handles of higher value than the inclusive price change will be charged extra on basis of requirement , size, quantity ,time.
- The electrical breakup will be provided post-design with detailed specifications. Wires will be from Anchor or Polycab, lights from Philips, GM, or as per client recommendations, and switches will match those provided by the builder. Electrical work includes a 2-year warranty. Additional fittings after work completion will be charged as per actuals.

Payment Breakdown

PAYMENT	PERCENTAGE	AMOUNT (Rs.)
Booking advance - 3% or INR 15000/- whichever is higher (Design Phase)	3%	31,082.00
2nd Payment - 50% of final amount (Before Production)	47%	4,86,946.00
3rd Payment - 40% of final amount (After material to site)	40%	4,14,422.00
4th Payment - 7% of final amount (Before handover)	10%	1,03,605.00

Additional Notes

Material Specification:- The ply used for the kitchen carcass is BWP 710 Grade Century Sainik.

- The ply used for other carcass is MR 303 Grade Century Sainik.
- All hinges and channels are from Hettich/EBCO, soft closing, unless specified. Additional charges: Hinges Ebco: ₹180; Hinges Hettich: ₹380; Channels Ebco: ₹690; Channels Hettich: ₹850 ; Loft hinges and Wardrobe internal drawers will be normal closing unless specified.
- Ply used for Side and Middle Panels will be 16mm Ply with 18mm output and Back Panel will be 6mm Ply.
- Ply used for Swing Doors will be 18mm Ply / 16mm Ply or HDHMR (based on customer discussion), and Ply used for Sliding Doors will be with Block boards or HDHMR (20mm/18mm).
- Door Stiffeners cost will be Added based on door size (additional charges apply).
- External finish for wardrobe: Laminates of Merino, Century, Welvin, or equivalent (High Glossy/Textured), up to ₹1500 included in the per sq. ft. cost.
- Internal finish: 0.8mm standard laminate – off white, fabric laminate will be charged additional.
- All SS baskets are from 304-grade rust-proof material.
- Locks will be from Godrej, Europa, or Ebco (subject to availability).
- Hydraulic lift-ups will be from Ebco unless mentioned in the quotation.
- Push magnets: will be from Ebco unless mentioned in the quotation.
- False ceiling: POP-Gypsum board from Saint Gobain with ultra-channels, measured on an RFT (running square feet) basis. Asian Premium emulsion paint will be considered for gypsum areas. Electrical work is additional if not included in the quotation.
- Mirrors/Glass: From Saint Gobain.
- Handles: Cost range included for Loft areas: ₹100-130; Wardrobes: ₹180-200;
- The electrical breakup will be provided post-design with detailed specifications. Wires will be from Anchor or Polycab, lights from Philips, GM, or as per client recommendations, and switches will match those provided by the builder. Electrical work includes a 2-year warranty. Additional fittings after work completion will be charged as per actuals.

Terms & Conditions

- 3D views are for representation only, and actual products may vary based on site conditions.
- Any new work or deviation from the quotation, such as changes in sizes or materials, will be charged based on the unit value and added to the project cost.
- Any additional work not included in the quotation will require 100% advance payment, charged as per actuals, and may require additional timelines mutually agreed upon.
- Any extra work or changes may require additional time, which will be communicated during execution. • Only the glass works mentioned in the quotation are included. Glass works for other areas in the flat are not included.
- Wardrobe gaps caused by wall undulations will be filled with putty or silicon.
- Each wardrobe quotation includes 2 drawers for every 3 feet of wardrobe as part of the standard offering. Any additional drawers required beyond this allocation will incur extra charges unless explicitly specified in the quotation.
- Civil, electrical, or plumbing works are not included in the quotation unless explicitly specified.
- Timelines depend on the client's cooperation in material selection and addressing other dependency works.
- Additional time may be required for delays caused by unavoidable circumstances, such as material unavailability, stock issues, strikes, power outages, special permissions, lockdowns, or builder-related issues.
- Finalized designs cannot be changed once the site work has commenced.
- Facilities like water, electricity supply, site cleaning, and scaffolding must be provided by the client or paid for additionally as needed. Cleaning is handled by Int360, but any special requests will incur additional charges.
- Unloading will be free if a service lift is available. If goods need to be carried upstairs, extra charges will apply.
- Accessories like rolling shutters, pantry units, and magic corners will be charged extra if not specified in the quotation.
- Electrical appliances, such as chimneys, hobs, lights, and fans, are not included unless explicitly mentioned.
- Any item not listed in the quotation will be included in the final bill if executed or used during the project.
- Int360 will not be liable for damages to old items (e.g., granite, sinks, glasses) during removal if they are intended to be reused.
- Floor protection will be charged as per actual costs if not included in the quotation.
- Painting or touch-up work on the house is necessary after completing the interior work. This will be charged additionally if it is not explicitly mentioned in the quotation.
- If painting is done by an external team or the client, INT360 is not responsible for unit damage; woodwork must be approved beforehand. Covering units incurs extra charges, and floor mark cleaning is the painting team's responsibility.
- The quotation is valid for one month from the date of signup. Price lock up to 6 months is available once the customer locks in with us for interiors by paying the booking fees
- Warranty applies to: Ceiling, hardware, woodwork, and laminates installed by Int360.
- Warranty exclusions: Items like glass, handles, painting, or materials purchased by the customer or third-party vendors but installed by Int360.
- The woodwork warranty will be null and void, and INT360 will not be responsible for any damage resulting from continuous water seepage, dampness, misuse, normal wear and tear, negligence, or any dismantling and shifting done by individuals other than INT360's authorized and qualified carpenters. INT360's decision regarding the cause of damage, whether due to seepage, dampness, misuse, wear and tear, or negligence, will be considered final and binding on the client.
- Cost for packing of the furniture for painting is not covered

This document is system-generated by TatvaOps and does not require a physical signature.